

Stevenage – Embankment Stabilisation

| Project | JJM2642 – Adoptable Roads Stabilisation | | | | |
|---------------------|--|--|--|--|--|
| Location | Marham Park Bury St Edmunds | | | | |
| Client | Orbital Homes | | | | |
| Key works delivered | Capping and Sub Base Replacement - Stabilisation | | | | |
| Project Duration | March 2022 | | | | |
| Stabilised Area | 5,000m2 | | | | |
| Earthworks | By MC | | | | |



PROJECT OVERVIEW

- Adoptable Estate Road identified as suitable for Capping replacement by Stabilising the site won excavated material
- Excavated material on site to be shifted and In-situ treat material laid in layers to provide a 9E or 9F Capping Layer - 450mm deep in two layers with Lime and Cement in Class 6R or 71 material to achieve min 15% CBR, 95% Compaction (2.5kg Rammer) & HSV's > 60kPa.
- Client requirements 95% Compaction and 30% CBR Non Frost Susceptibility
- JJMac tested and classified the material as suitable to achieve these requirements

643 (02/16) Lime and Cement Stabilisation to Form Capping

1 (02/16) Where capping is to consist of, either wholly or in part, lime and cement stabilised material Class 9E or 9F, this Clause shall apply to the construction of those parts which are stabilised with lime and cement.

2 (02/16) Material to be stabilised with lime and cement shall be Class 6R or 7I material all complying with Clause 601 and Table 6/1.



PROJECT CHALLENGES

The project was very challenging as the drainage had been installed prior to Stabilisation. Mellowing of the lime mix was min 24hrs, so time management and coordination was a key requirement from all parties on site to ensure an efficient operation and highest quality was always maintained.

Poor CBR % at formation level would require careful working with heavy machinery not to damage the formation.

| | TEST REPORT Soil Property Testing Ltd | | | | | | | |
|---------------------------------------|--|--|---------------|-------------------|-------------------------------|--|-----------------------|------------------------------------|
| | | Date of Issue | as page 1 | | | | | Page 4 of 5 |
| | | Contract | Parcel F, Ma | rham Park, | Bury St Edmu | unds. | | |
| | | Serial No | 39570_1 | | | | Date of Test: | 11/10/2021 |
| PRIMA LIGHT WEIGHT DEFLECTOMETER TEST | | | | | | | | |
| | | FOUND | ATION SU | RFACE N | AODULUS | (Emod) – | STIFFNESS – MPa | • |
| _ | Approx | imate Location | Emod (MPa) | kNmm ² | Average Deflection (µm) | Average CBR of three test drops | Surface Material | Surface Moisture / Observations |
| Test No | Chainage | Position | | | | | | |
| 1 | 40 | Left hand side of roadway 1.0m from kerb edge | 24.60 | 0.025 | 1154 | 2.4 | Light grey Chalk MARL | Damp 5.8 ^o C |
| 2 | 40 | Right hand side of roadway 1.0m from kerb edge | 23.03 | 0.023 | 1163 | 2.3 | Light grey Chalk MARL | Damp 5.8 ⁰ C |
| 3 | 50 | Left hand side of roadway 1.0m from kerb edge | 20.52 | 0.021 | 1402 | 2.0 | Light grey Chalk MARL | Dry 7.2 ⁰ C |
| 4 | 50 | Right hand side of roadway 1.0m from kerb edge | 19.84 | 0.200 | 1431 | 1.9 | Light grey Chalk MARL | Dry 7.2 ⁰ C |
| 5 | 50 | Left hand side of roadway 1.0m from kerb edge | 27.50 | 0.021 | 908 | 2.8 | Light grey Chalk MARL | Dry 7.2 ⁰ C |
| 6 | 50 | Right hand side of roadway 1.0m from kerb edge | 27.01 | 0.027 | 917 | 2.6 | Light grey Chalk MARL | Dry 7.2 ⁰ C |
| 7 | 20 | Left hand side of roadway 1.0m from kerb edge | 33.48 | 0.033 | 835 | 3.3 | Light grey Chalk MARL | Dry 8.4 ^o C |
| 8 | 20 | Right hand side of roadway 1.0m from kerb edge | 31.62 | 0.032 | 857 | 3.1 | Light grey Chalk MARL | Dry 8.4 ⁰ C |
| Remarks | Tests carried out at various locations along the length of the carriageway at the top of the foundation as instructed by the client. | | | | | | | cted by the client. |
| Date | | Time | Engir | neer | | In-Hou | se Calibration | Conditions |
| 11/10/2021 | | 10:30 | A Butcher B | Sc (Hons) | | (| Checked | Clear 17 ^o C |
| LMD Head | | Prima 100 Sarial No. PMC | 2020002 | | Next mar | sufacturers calibr | ation due: 26/03/2022 | |

ENGINEERING AND SOLUTIONS TO OVERCOME THE CHALLENGES

To overcome the project challenges set by the client, our team:

- Worked with the client and advised on the findings of the site won material testing and classification.
- The challenge was to spread and stabilise the excavated material by mixing with Cement and complying with the stringent testing schedule for the stabilised material.
- Our site team set to work with the MC team to develop a system to allow both earthworks and stabilisation to progress efficiently.



Stabilisation during Construction Phase

Agile equipment utilised for the tight working conditions in and around the drainage Fendt tractor and Stehr Tractor mounted Stabilisation Mixer





Completed Works

Stabilised Capping Replacement sealed with Bitumen Tack Coat





CBR Report on Finished Stabilised Surface



Contract

as page 1 Marham Park Road 3a

TEST REPORT Soil Property Testing Ltd

| | | Serial No | 39825_1 | | | | Date of Test: | 11/10/2021 |
|--|----------------------|--|-------------------------|-------|-------------------------------|--|-------------------------|------------------------------------|
| PRIMA LIGHT WEIGHT DEFLECTOMETER TEST FOUNDATION SURFACE MODULUS (Emod) – STIFFNESS – MPa | | | | | | | | |
| | Approximate Location | | | | Average Deflection (µm) | Average CBR of three test drops | Material | Surface Moisture / Observations |
| Test No | Chainage | e Position | (MPa) kNmm ² | | | | | |
| 1 | 5 | Left hand side of roadway 1.0m from kerb edge | 463.80 | 0.464 | 58 | 166.0 | stabalised road surface | Dry 14°C |
| 2 | | Centre line of roadway | 454.33 | 0.454 | 59 | 160.7 | stabalised road surface | Dry 14°C |
| 3 | | Right hand side of roadway 1.0m from kerb edge | 472.23 | 0.472 | 56 | 170.7 | | |
| 4 | 10 | Left hand side of roadway 1.0m from kerb edge | 469.27 | 0.469 | 57 | 169.0 | | |
| 5 | | Centre line of roadway | 476.13 | 0.476 | 56 | 172.9 | | |
| 6 | | Right hand side of roadway 1.0m from kerb edge | 485.70 | 0.486 | 55 | 178.4 | | |
| 7 | 15 | Left hand side of roadway 1.0m from kerb edge | 543.80 | 0.544 | 50 | 212.8 | | |
| 8 | | Centre line of roadway | 553.27 | 0.553 | 49 | 218.6 | | |
| 9 | | Right hand side of roadway 1.0m from kerb edge | 552.47 | 0.552 | 49 | 218.1 | | |
| 10 | 20 | Left hand side of roadway 1.0m from kerb edge | 360.27 | 0.360 | 74 | 111.8 | | |
| 11 | | Centre line of roadway | 314.77 | 0.315 | 85 | 90.6 | | |
| 12 | | Right hand side of roadway 1.0m from kerb edge | 412.53 | 0.413 | 67 | 138.2 | | |



ADVANTAGES

The works had numerous advantages to this site.

- Utilise site won material from Excavations for Modification
- Elimination of Primary Aggregates for making up levels
- Elimination of Primary Aggregate and Lorries from the surrounding Roads

BENEFITS TO CLIENT

| Cost Saving | | |
|--------------------------------------|-----|------|
| | 60% | |
| Programme Reduction | | |
| | 70% | |
| Vehicle Movements Reduction | | |
| | | 95% |
| Imported Aggregate Reduction | | |
| | | 90% |
| Material Sent To Landfill Reduced By | | |
| | | 100% |
| Stone Layer Depth Reduction | | |
| | 75% | |